

# 42' X 40' GEN3™



INSTALL TIME:

**2-3 HOURS**



REQUIRED PERSONNEL:

**4-5 CREW**



AXLE RATING:

**25,000 LB X 2**

## WHY OPERATORS CHOOSE THE 4240 GEN3™ MOBILE HYDRAULIC STAGE

### YOU GET MORE WITH APEX

Well-thought-out Design,  
Durable Build & Streamlined  
Great Looks all in an affordable  
high quality mobile hydraulic stage.

### FULL 40' SPAN BETWEEN CORNER SUPPORT TOWERS

No need to piece together  
odd lengths of rigging truss.

### UNOBSTRUCTED LOAD IN/OUT FOOTPATH

Floor panels feature a full  
16' space between masts  
and corner towers.

### SYMMETRICAL DUAL STAGE POSITIONING

Either side can be the front of  
the stage, and speakers can be  
hung on either side.

### #1 FOR EASY TRANSPORT

Traditional semi-trailer  
engagement provides unequalled  
maneuverability in a  
40' mobile stage.

### VERY SAFE

APEX Stages have a spotless  
safety history and are Engineer  
Certified in all 50 states, plus  
many Canadian Provinces.

#### SALES/SERVICE

3305 Airport Circle, Pittsburg, KS 66762  
Phone: 620-235-1712 | Fax: 620-235-1772  
sales@apexstages.com  
www.apexstages.com

#### SALES REPRESENTATIVE

Jeff Hess  
Progressive Products, Inc.  
Phone: 417-438-0213  
jhess@progressiveproductsinc.com

**CONTACT  
US FOR A  
QUOTE ►**





# SPECIFICATIONS



INSTALL TIME:  
**2-3 HOURS**

## TRAILER (UNOPENED)

|                |             |
|----------------|-------------|
| Length         | 45' 6"      |
| Width          | 102"        |
| Height         | 12' 4"      |
| Cargo Space    | 6' X 39' 6" |
| Cargo Capacity | 2,000#      |
| Trailer Weight | 48,000#     |
| Tongue Weight  | 20,000#     |
| Axle Rating    | 25,000# X 2 |

## STAGE DECK

|                           |                     |
|---------------------------|---------------------|
| Floor Size                | 42' X 38'           |
| Floor Height (Adjustable) | 55" – 72"           |
| Ground to Roof            | 31' 6"              |
| Structure                 | Marine Plywood/Alum |
| Floor Support             | 34 – 8,000# Jacks   |



REQUIRED PERSONNEL:  
**4-5 CREW**

## STAGE ROOF

|                                  |                   |
|----------------------------------|-------------------|
| Coverage                         | 44' 10" X 39' 10" |
| Deck to Roof Top                 | 27' 5"            |
| Deck to Downstage I-Beam         | 25'               |
| Deck to Center-Stage I-Beam      | 25' 4"            |
| Deck to Bottom of Upstage I-Beam | 25'               |
| Surface Mat                      | Fiberglass/Alum   |

## ROOF BEAM LOADS

|                       |            |
|-----------------------|------------|
| Angle Fly Bay Support | 4 @ 2,000# |
| Fly Bays              | 4 @ 4,000# |
| Downstage I-Beam      | 7,260#     |
| Center I-Beams        | 2 @ 7,090# |
| Upstage I-Beam        | 7,260#     |
| Intermediate I-Beam   | 2 @ 3,000# |
| Roof Capacity         | 58,700#    |

## OTHER

|                         |                      |
|-------------------------|----------------------|
| Site Preparation        | None                 |
| Hauling Mode            | Kingpin Hitch (Semi) |
| Power Source (Standard) | 20 HP Electric 110   |

*"We are the most prolific event production company in south Florida and we own every model of APEX stage."*

**THOMAS MITCHELL, OWNER**

REFLECTIONS PRODUCTIONS  
IN MIAMI, FLORIDA